

An Innovative Low-Energy Technology Application at MCB Camp Pendleton

May 13, 2010

Arun Gavaskar (presenter) NAVFAC Atlantic

> Theresa Morley * NAVFAC SW

Thomas Spriggs NAVFAC Atlantic

* Primary Project Lead



Overview of the Box Canyon Landfill GSR Project



- Location of Box Canyon (Site 7) Landfill
- History of Site 7 Landfill
- Laying the Groundwork to Use GSR
- Challenges to Incorporating GSR Projects
 - Regulatory Acceptance
 - Construction on Existing Landfill Cap
- GSR Projects at MCB Camp Pendleton's Landfill, Site 7
 - Photovoltaic Project
 - Methane Micro-turbine Project

Regional Location of MCB Camp Pendleton





Specific Location of Box Canyon (Site 7) Landfill





History of the Box Canyon (Site 7) Landfill



- Landfill encompasses a 28-acre open area
- CAMU built next to a housing and elementary school on open municipal landfill
- Later lawsuit resulted in the only toxic tort case in Navy's history
- Area continues to be a source of constant concern to State agencies
- Monitored methane gas levels fluctuate in and out of compliance
- Ongoing activities:
 - Landfill gas monitoring
 - Groundwater monitoring
 - Site maintenance



Laying the Groundwork for GSR Projects at the Site 7 Landfill



- Idea for photovoltaic (PV) panels onsite came from Mike Montgomery (Region IX Branch Chief) on a site tour
- MCB Camp Pendleton submitted request for \$10M from the American Recovery and Reinvestment Act (ARRA)
 - Many strings attached, including an expedited schedule
 - Design complete, construction must start no later than 6 months after award
- Met with legal counsel, base, EPA and their attorneys to negotiate an ESD instead of a ROD Amendment
- Presented concept to the remaining Federal Facilities Agency (FFA) members supported by the EPA – important to note – resulting in a change in land use, not a remedy

Aerial View of Site 7 Landfill





Agency Concerns to Incorporating GSR



Construction on an Existing Landfill Cap

- Settlement
- Bearing capacity of soil
- Stability
- Displacement
- Controlling erosion/soil loss
- Drainage control
- Infiltration
- Site access
- Landfill gas control system (not affected by design)

Site 7 Landfill Cap Drainage Plan



Design Specifications to Address Agency Concerns

Infiltration

- Approved vegetation list provided by NAVFAC SW biologist
 - Array area: short growth (<3 ft tall) & shade tolerant
 - In-between rows: "hearty" vegetation
- During construction, minimize disturbance to existing vegetation
- Conduct system O&M every 6 months, including vegetation checks

Site Access

- Existing improved surfaces will remain
- No additional improvements will be needed

Photovoltaic (PV) System Design Specs



Photovoltaic Design Specifications

- 1.48 MW (DC) capacity
- System made up of 220, 28-module 6.6 kW building blocks
- Each panel has a fixed 15° tilt, 190° orientation

Construction Specifications

- Units are built on self-ballasted, non-penetrating foundations
- Gravel interface between ballasts and landfill cover
- Adjustable system structure components
- Spacing between modules (maintenance)
- No excavation of the existing ET cover

Photovoltaic Layout Plan (~50% Design)





Site 7 Landfill P/V & Transmission Plan





FIGURE REFERENCE: PRELIMINARY DESIGN PROVIDED BY MCB CAMP PENDLETON SCC390401. TS.DB solar panel.ai 7/09

- CH2MHILL

Naval Facilities Engineering Command

Methane Gas Collection: Microturbine System Design Specs

- GeoSyntec approached the Navy with GSR solution for continuing methane problem
- Proposed a 30kW microturbine connected to methane gas collection wells and energy produced fed into PV panel system
- Microturbine is the size of an industrial refrigerator
 - Cannot see unit from the housing complex or school
 - Unit runs quiet w/o a flare; optional night operation
- System most adaptable to low methane production and fluctuations in gas volumes



CR30 MicroTurbine

Methane Gas Flow





Proposed Gas Collection Layout





Proposed Gas Collection and Energy Production Schematic









- Exciting opportunity to incorporate GSR on an existing, open IR site, i.e., 'clean slate'
- Key to success was working with other agencies to meet Navy sustainability goals
- Key design criteria critical to success:
 - Counter-balanced, non-penetrating foundations will avoid construction into the existing landfill cap
 - High efficiency, fixed orientation, and modular PV cell units
 - Incorporating appropriate vegetation for use around PV cells
 - State-of-the-art microturbine capable of running efficiently at low methane concentrations (~7%)
 - Utilizing two GSR technologies at the same facility



- Disturbs pristine desert environments (not an issue with landfills)
- •May require cooling water, which is hard to find in deserts (the sunniest areas)
- A single solar panel generates very little electricity, so vast array is required
- Mechanical system required to keep panels adjusted towards the sun at all times
- •Maintenance costs, weathering of expensive panels under the impact of the elements will need to be studied
- •Need supplemental source of power during cloudy days, nights
- •Carbon neutrality needs to be established on the basis of life cycle analysis. Specialty chemicals that go into solar panel manufacture have their own carbon footprint.



- •11 operational projects (land fill gas microturbines)) in California, utilizing 50 turbines, generating 2.7 MW of power
- Microturbines use 35% more fuel per kWH produced, compared to standard reciprocating engines and conventional turbines (US EPA, 2002)
- Energy produced may be sporadic, supplemental sources of power needed
- •Maintenance requirements need to be tracked in the future
- •Compressed landfill gas projects may also be worth looking at

Follow-up Contacts



MCB Camp Pendleton RPM: Theresa Morley, NAVFAC SW <u>Theresa.Morley@navy.mil</u> (619) 532-1502

Green & Sustainable Remediation: Tom Spriggs, NAVFAC LANT <u>Thomas.Spriggs@navy.mil</u> (757) 322-4335